




1 HARD CEILING MOUNT
T1.6.2 SCALE: NTS




4 SAFETY WIRE
T1.6.2 SCALE: NTS




5 HARD CEILING MOUNT (14- FEET OR LESS)
T1.6.2 SCALE: NTS




2 BUILDING STEEL MOUNT
T1.6.2 SCALE: NTS




6 PATCH CORD ROUTING
T1.6.2 SCALE: NTS



7 16- FEET AND UNDER DROP CEILING MOUNT
T1.6.2 SCALE: NTS



3 MOUNTING WHEN BUILDING STRUCTURE IS INACCESSIBLE
T1.6.2 SCALE: NTS



8 DROP CEILING MOUNT OPTION 2
T1.6.2 SCALE: NTS

ZAP MOUNTING NOTES:

1. WHEN MOUNTING TO A CONCRETE CEILING USE TAPCON OR DRIVE ANCHORS RATED TO SUPPORT 500lbs. WHEN MOUNTING TO A DRYWALL CEILING BE SURE TO ANCHOR TO A CEILING JOIST. (DO NOT USE DRYWALL ANCHORS)
2. DRILL A 1/2-INCH DIAMETER HOLE IN THE TOP OF THE CONDUIT SO THE 1/4-20 x 3/4" PAN HEAD BOLT WILL BE FLUSH TO THE INSIDE BOTTOM OF THE CONDUIT AND DRILL A 1/4-INCH DIAMETER HOLE IN THE BOTTOM OF THE CONDUIT TO MOUNT THE MOTOROLA AP BRACKET.
3. ZIGBEE AP's (ZAP's) SHOULD BE TO THE RIGHT OF THE AP's WHEN STANDING IN FRONT AND LOOKING TOWARDS THE BACK OF THE STORE. THE RED LIGHT ON THE BOTTOM OF THE ZAP's SHOULD BE TOWARDS THE BACK LEFT OF THE STORE. THE LAN PORTS ON THE AP's SHOULD BE TOWARDS THE BACK OF THE STORE.
4. SAFETY WIRE SHALL BE FIRMLY ATTACHED TO THE HARD CEILING OR BUILDING STRUCTURE. THEN FEED INTO THE 4x4 SQUARE BOX AND DOWN THRU THE 3/4" CONDUIT. EXIT THE SINGLE GANG BOX AND FEED THRU THE SAFETY EYELET ON THE MOTOROLA AP. THEN WRAP TWICE AROUND THE AP MOUNTING BRACKET AND 3/4" CONDUIT.



MICHIGAN
RE-FRESH FARE

THIS DRAWING IS INTENDED ONLY TO SHOW THE REQUIREMENTS OF THE DESIGN. CO. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION AND MAINTENANCE OF THE SYSTEM. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION AND MAINTENANCE OF THE SYSTEM.

40393 Grand River Avenue
Newport, Michigan
PHONE: (248) 957-2254 FAX: (248) 957-2255



GENERAL OFFICE
FACILITY ENGINEERING
3000 W. GRIFFIN AVE. SUITE 200
ANN ARBOR MI 48106

TAKEOVER IFB
D-361
425 NORTH CENTER
NORTHVILLE, MI

CURRENT PLAN DATE
7/12/15

ORIGINAL PLAN DATE
5/22/2015

DRAWN
J. EDWARDS

CHECKED
D. BUSAM

REVISIONS:

STANDARD PLOTTED SCALE
NONE

BUILDING STATS:

TOTAL SHELVING
1007 LF

SALES AREA
23,190 SF

BASE STORE
45 S

MEZZANINE
33,049 SF

DOCK / UTILITY
962 SF

GROSS BUILDING
2,388 SF

ZAP MOUNTING
DETAILS

STAIR PACKAGE
Not Applicable

D-361

T1.6.2

CAD FILE