

ALL HVAC SENSORS (I.E. ANALOG TEMPERATURE SENSORS, RELATIVE HUMIDITY SENSORS, CO2 SENSORS) TO BE MOUNTED AT 7'-6" ABOVE FINISHED FLOOR.

LIGHTING OVERRIDE SWITCHES TO BE MOUNTED AT 6'-4" ABOVE FINISHED FLOOR.

