


MEZZANINE PLAN
SCALE: 3/32" = 1'-0"




LIGHTING DEMO PLAN
SCALE: 3/32" = 1'-0"

DEMOLITION PHASE #2 ITEMS:

THIS WORK IS THE RESPONSIBILITY OF THE GC. DURING THE REMODEL CONSTRUCTION OF THE PROJECT.

1. ALL EXTERIOR BUILDING OPENINGS (REMOVAL OF EXISTING EXTERIOR WALLS, DOORS, GLAZING, ETC.)
2. REMOVAL OF ALL ROOF TOP ITEMS (RTUs, EXHAUST FANS, FLUES, VENT STACKS, CONDENSERS, ETC.). PATCH AND REPAIR ROOF, INFILL METAL DECK AS REQUIRED AFTER REMOVAL OF ROOF TOP ITEMS.
3. REMOVE THE PRIMARY ELECTRICAL COLUMN AND ASSOCIATED ITEMS AFTER INSTALLATION OF THE NEW PRIMARY ELECTRICAL FEED ON THE EXTERIOR OF THE BUILDING.
4. ALL EXTERIOR SITE DEMOLITION WORK. (THIS IS TO INCLUDE CONCRETE REMOVAL FOR MASS SLAB FOOTINGS, NEW SIDEWALK RAMPS, ETC.)
5. REMOVAL OF TOP COURSE OF PARKING LOT ASPHALT TO ALLOW FOR NEW TOPPING COURSE ASPHALT.
6. G.C. TO REPAIR AND/OR REPLACE ALL SHEATHING, FRAMING AND/OR FINISHES AS REQUIRED DUE TO DEMOLITION WORK. COORDINATE WITH ALL DEMOLITION PLANS (ARCHITECTURAL, MECHANICAL, PLUMBING, & ELECTRICAL)



GENERAL NOTES

1. REMOVE OR RELOCATE EXISTING ELECTRICAL WORK AS REQUIRED TO ACCOMMODATE NEW WORK.
2. REMOVE AND RELOCATE EXISTING ELECTRICAL WORK FROM SURFACES OR WITHIN WALLS TO BE REMOVED TO NEAREST EXISTING WALL TO REMAIN OR NEW WALL AS REQUIRED. DO NOT LEAVE EXISTING ELECTRICAL WORK FREESTANDING IN AREAS INTENDED TO BE CLEAR SPACE. CONCEAL WHERE PRACTICABLE.
3. REMOVE AND RELOCATE EXISTING ELECTRICAL WORK ABOVE EXISTING SUSPENDED CEILINGS TO BE REMOVED. INSTALL AS TIGHT TO EXPOSED DECK AS PERMITTED BY CODE.
4. REMOVE EXISTING ABANDONED ELECTRICAL WORK ABOVE EXISTING SUSPENDED CEILINGS TO BE REMOVED.
5. REMOVE ALL INTERIOR LUMINAIRES, WIRING METHODS, AND DEVICES AS REQUIRED IN AREAS SHOWN. REMOVE 11 OF 14 ROWS IN SALES AREA, LEAVING 3 ROWS FOR TEMPORARY LIGHTING.

- FOR REFERENCE ONLY -

ALL WORK ON THE DEMOLITION DRAWINGS ARE FOR REFERENCE ONLY AND HAVE BEEN COMPLETED EXCEPT FOR THE ITEMS INDICATED AS PHASE #2. PHASE #2 ITEMS ARE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR. REFER TO 'DEMOLITION PHASE #2 ITEMS'

| | |
|--|-----------|
| BIDS & PERMITS 06-28-2015 | |
| DEMOLITION ADDENDUM No. 1 06-24-2015 | |
| DEMOLITION BIDS & PERMITS 06-18-2015 | |
| ISSUED FOR: | |
| PROPOSED INTERIOR REMODEL FOR: | |
|  | |
| STORE NO. D-361 | |
| 425 N. CENTER STREET NORTHVILLE, MI 48167 | |
| THE KROGER CO. OF MICHIGAN | |
|  | |
| jeffery a. scott architects p.c. | |
| 32316 grand river ave. suite 200 farmington, michigan 48336-3261 (248) 476-8800 fax (248) 476-8833 | |
| LIGHTING DEMO PLAN | |
| project no. | sheet no. |
| 15100 | ED1.1 |