



NOTES

1. ALL HVAC SENSORS (I.E. ANALOG TEMPERATURE SENSORS, RELATIVE HUMIDITY SENSORS, CO2 SENSORS) TO BE MOUNTED AT 7'-6" ABOVE FINISHED FLOOR.
2. LIGHTING OVERRIDE SWITCHES TO BE MOUNTED AT 6'-4" ABOVE FINISHED FLOOR.
3. A MODBUS REPEATER IS NEEDED AFTER EVERY 32 CASE CONTROLS IN A ~~FLOOR~~ DOOR ALARM OUTPUTS TO BE WIRED TO THE SPARE DIGITAL INPUT OF CASE CONTROLLER. MULTIPLE EVAPORATORS IN A BOX SHOULD BE DAISY-CHAINED TOGETHER.
4. ISLAND DESIGNATED AS DUAL TEMP WILL HAVE AN OEM INSTALLED TOGGLE SWITCH ON EACH SECTION WIRED TO THE RESPECTIVE CASE CONTROLLER SPARE DIGITAL INPUT.



| | | | |
|--|--|--|--|
| BIDS AND PERMITS 90% OWNER REVIEW | | 12/13/2023 10/28/2023 | |
| PROPOSED MINOR INTERIOR REMODEL FOR: | | | |
|  | | | |
| STORE NO. D-361 425 N CENTER ST NORTHTVILLE, MI 48167 | | | |
| THE KROGER CO. OF MICHIGAN | | | |
|  | | jeffery a. scott architects p.c. | |
| 32316 grand river ave. suite 200 farmington, michigan 48336-3261 (248) 476-8800 fax (248) 476-8833 | | | |
| ENERGY MGMT TERM DETAILS | | | |
| project no. | | sheet no. | |
| 23101 | | EM-2B | |