



ALSO SEE ASD-69,
SHEET A5.1.1

Diagram illustrating a roof-to-wall penetration detail. The components shown are:

- WATER CUT OFF MASTIC
- STAINLESS STL. CLAMP RING
- LAP SEALANT
- SINGLE PLY MEMBRANE
- ROOF INSULATION
- PREMOLDED PIPE SEAL
- 1/2" TO 6 1/2" DIA. PIPE SIZE
- 6" JOIST
- 6" STACK OR PIPE

SAWCUT AROUND EXISTING REFRIGERATION PIT AS REQUIRED TO REMOVE THE PIT & FRAME, CAP THE EXISTING PIPES, AND INFILL WITH NEW FILL & CONCRETE SLAB.

EXISTING SLAB

NEW CONCRETE SLAB

SEE DETAIL 'A' ON CONTROL JOINT DETAIL 529, SHEET A5.2

REMOVE EXISTING PIT COVER COMPLETE

NEW 4" CONCRETE: USE HIGH-EARLY CONCRETE.

VAPOR BARRIER OVER 4" GRANULAR FILL

ABANDONED EXISTING PVC OR ABS PIPES FOR REFRIGERATION LINES

INFILL WITH FIRM SOIL

SECURELY CAP EXISTING PIPES.

REMOVE EXISTING REFRIGERATION PIT COMPLETE.

REMOVE ALL ABANDONED & UNUSED REFRIGERATION LINES FROM EXISTING PIPES.

ABANDONED EXISTING PVC OR ABS PIPES FOR REFRIGERATION LINES

REMOVE EXISTING PIT COVER COMPLETE.

EPOXY COATED DEFORMED TIE BAR - 16" O.C. PLACE BAR 8" INTO EACH SLAB.

CORE AND EPOXY ANCHOR INTO EXISTING SLAB

SEE RISO-34A, ON SHEET R5.1 FOR WALL MOUNTED REFRIGERATION PIPING.

MATERIAL & FINISH PER PLANS, PARTITION TYPES, & FINISH SCHEDULE.

REFRIGERATION PIPES

SALES OR PREP AREA

GROUP REFRIGERATION LINES TOGETHER FOR CONTINUOUS CASE LINE-UPS. COORDINATE WITH REFRIGERATION DRAWINGS & REFRIGERATION CONTRACTORS

MATERIAL & FINISH PER PLANS, PARTITION TYPES & FINISH SCHEDULE.



REFRIGERATION PIPES

SEE RISO-34 ON SHEET R5.1 FOR WALL MOUNTED REFRIGERATION PIPING.

STAGING AREA

1/2" FRT PLYWOOD, FULL HEIGHT OF WALL, WIDTH TO SUIT STUD SPACING.

NOTE:
TYPICAL WHERE REFRIGERATION LINES ARE RUN UP WALLS. PATCH/REPAIR EXISTING WALLS AS REQUIRED DUE TO DEMOLITION & INSTALLATION/MODIFICATION OF REFRIGERATION PIPES.

Issued for: <div style="border: 1px solid black; padding: 5px; text-align: center;"> BIDS AND PERMITS 90% OWNER REVIEW </div>	<div style="text-align: right;"> 02/27/2024 01/17/2024 </div>
<p>PROPOSED MINOR INTERIOR REMODEL FOR:</p> <div style="text-align: center; margin: 20px 0;">  </div> <p>STORE NO. D-707 2010 WITTAKER ROAD YPSILANTI, MI 48197</p> <p>THE KROGER CO. OF MICHIGAN</p>	
<div style="display: flex; align-items: center; justify-content: center;">  <div> <p>jeffery a. scott</p> <p>architects p.c.</p> </div> </div>	
<p>32316 grand river ave. suite 200 farmington, michigan 48336-3261 (248) 476-8800 fax (248) 476-8833</p>	
<p>PARTITION TYPES, DETAILS & NOTES</p>	
project no. <div style="border: 1px solid black; height: 150px; margin-top: 10px; display: flex; align-items: center; justify-content: center; font-size: 48px; font-weight: bold;"> 23044 </div>	sheet no. <div style="border: 1px solid black; height: 150px; margin-top: 10px; display: flex; align-items: center; justify-content: center; font-size: 48px; font-weight: bold;"> A5.2 </div>