



PLUMBING GENERAL NOTES:


1. REFER TO NOTES ON SHEET P5.1.
2. PROVIDE NEW PLUMBING SERVICES TO FIXTURES AS INDICATED ON PLUMBING FIXTURE SCHEDULE (RE: P5.1).
3. WHERE MULTIPLE DRAINAGE FIXTURES ARE SERVED BY A SINGLE HUB DRAIN, PROVIDE CONCENTRIC 4" COUPLING ON HUB OPENING.
4. REFER TO PLUMBING DETAILS ON SHEETS P5.1.



1A SANITARY & VENT ENLARGED PLAN
SCALE: 1/8" = 1'-0"




1B DOMESTIC WATER ENLARGED PLAN
SCALE: 1/8" = 1'-0"



2 PLUMBING ENLARGED PLAN
SCALE: 1/8" = 1'-0"

KEYED NOTES:

1. PROVIDE NEW 3" HUB DRAIN PER PSD-1 (RE: P5.1).
2. VERIFY EXACT LOCATION OF EXISTING 3" HUB DRAIN. REUSE FLOOR DRAINAGE FIXTURE FOR NEW OR RELOCATED REFRIGERATED CASE.
3. INSTALL NEW BREAK ROOM SINK IN MILLWORK WITH VALVES AND FITTINGS AS REQUIRED. PROVIDE 1 1/2" DRAIN AND P-TRAP TO CONNECT TO EXISTING SANITARY CONNECTION. COORDINATE WITH ARCHITECTURAL TRADES.
4. INSTALL NEW COUNTERTOP SINKS. CONNECT TO EXISTING SANITARY AND WATER SUPPLY ROUGH-IN CONNECTIONS. SEE SPECIFICATION 22-42.00 SECTION 2.3 "CONTRACTOR PROVIDED PLUMBING FIXTURES" FOR ACCEPTABLE MANUFACTURERS. REPLACE LAVS WITH ACCESSIBLE FIXTURES WITH HARD WIRED TOUCHLESS FAUCETS, SIMILAR TO EXISTING CONDITIONS.
5. INSTALL NEW TOILET ROOM FIXTURES. CONNECT TO EXISTING SANITARY AND CW SUPPLY ROUGH-IN CONNECTIONS.
6. INSTALL RELOCATED HAND SINK (PLHSWE) WITH FITTINGS AS REQUIRED. PROVIDE 2" SAN UP.
7. INSTALL RELOCATED 1-COMP SINK (PLIPC-18) AS PER PSD-5A (RE: P5.1). ROUTE 1 1/2" INDIRECT DRAIN TO FLOOR SINK, VENT WITH 2" AAV LOCATED BETWEEN OVENS UNDER HOOD.
8. RECONNECT EXISTING OVENS TO NEW HUB DRAIN AND EXISTING WATER SUPPLY ROUGH-IN CONNECTIONS.
9. ADJUST FLOOR DRAIN TO BE FLUSH WITH NEW FLOOR HEIGHT.



PLUMBING PLAN
SCALE: 1/16" = 1'-0"

BIDS AND PERMITS
02/27/2024
01/11/2024
90% OWNER REVIEW

PROPOSED MINOR INTERIOR
REMODEL FOR:

Kroger

STORE NO. D-707
2010 WITTAKER ROAD
YPSILANTI, MI 48197

THE KROGER CO. OF MICHIGAN

jeffery a. scott architects p.c.

32316 grand river ave. suite 200
farmington, michigan 48336-3261
(248) 476-8800 fax (248) 476-8833

PLUMBING PLAN

project no. 23044 sheet no. P1.1

copyright © 2024