

PLUMBING GENERAL NOTES:


1. REFER TO NOTES ON SHEET P5.1.
2. PROVIDE NEW PLUMBING SERVICES TO FIXTURES AS INDICATED ON PLUMBING FIXTURE SCHEDULE (RE: P5.1).
3. WHERE MULTIPLE DRAINAGE FIXTURES ARE SERVED BY A SINGLE HUB DRAIN, PROVIDE CONCENTRIC 4" COUPLING ON HUB OPENING.
4. REFER TO PLUMBING DETAILS ON SHEET P5.1.

KEYED NOTES:


1. PROVIDE NEW 3" HUB DRAIN PER PSD-1 (RE: P5.1).
2. VERIFY EXACT LOCATION OF EXISTING 3" HUB DRAIN. REUSE FLOOR DRAINAGE FIXTURE FOR NEW OR RELOCATED REFRIGERATED CASE.
3. INSTALL 1-COMP SINK (PL1PC-18/PL1R2-24) PER PSD-5A (RE: P5.1). ROUTE 1 1/2" INDIRECT DRAIN TO FLOOR SINK. INSTALL FLOOR SINK PER PSD-16B (RE: 5.1).
4. INSTALL 3-COMP SINK (PL3C-18NS) PER PSD-7 (RE: P5.1). ROUTE 2" INDIRECT DRAIN TO FLOOR SINK. INSTALL FLOOR SINK PER PSD-16B (RE: 5.1).
5. INSTALL HAND SINK (PLHSW) WITH FITTINGS AS REQUIRED. PROVIDE 1 1/2" DRAIN TO 2" SAN UP IN HALF WALL, VENT WITH 1 1/2" AAV LOCATED UNDERNEATH HAND SINK.
6. PROVIDE 2" VENT LINE UNDERGROUND TO WALL AND ROUTE IN HALF WALL TO NEW VENT STACK.
7. 2" VENT DOWN IN CHASE, CONNECT TO NEAREST EXISTING PLUMBING VENT PIPING. VERIFY EXACT LOCATION IN FIELD.
8. PROVIDE 1 1/2" VENT LINE UNDERGROUND TO WALL AND ROUTE IN WALL TO VENT STACK.
9. 1 1/2" VENTS DOWN IN WALL, CONNECT TO NEAREST EXISTING PLUMBING VENT PIPING. VERIFY EXACT LOCATION IN FIELD.

KEYED NOTES:

1. 3/4" HW & 3/4" CW DOWN TO SUSHI ISLAND IN NEW PVC CHASE. PAINTED TO MATCH COLUMNS. ROUTE LINES IN HALF WALL TO SERVICE FIXTURES.
2. ROUTE 3/4" HW & 3/4" CW LINE IN HALF WALL. TRANSITION TO PEX. ROUTE INSULATED TUBING UNDERGROUND TO NEW HALF WALL WITH 1-COMP PER DETAIL 1 (RE: P5.1). TRANSITION BACK TO STANDARD PIPING AND ROUTE TO PL1PC-18.
3. CONNECT GE235-2C TO EXISTING CW HOSE BIB ON WALL.



1 SANITARY & VENT ENLARGED PLAN  
P4.1 SCALE: 3/16" = 1'-0"



2 DOMESTIC WATER ENLARGED PLAN  
P4.1 SCALE: 3/16" = 1'-0"

BIDS AND PERMITS  
DIRECT BUY QUOTE  
90% OWNER REVIEW

03/06/2024  
02/19/2024  
01/25/2024

ISSUED FOR:

PROPOSED MINOR INTERIOR  
REMODEL FOR:

**Kroger**

STORE NO. D-711  
7084 MILLER ROAD  
SWARTZ CREEK, MI 48473

THE KROGER CO. OF MICHIGAN

**jeffery a. scott  
architects p.c.**

32316 grand river ave. suite 200  
farmington, michigan 48336-3261  
(248) 476-8800 fax (248) 476-8833

ENLARGED PLUMBING PLANS

project no. 23086 sheet no. P4.1

copyright © 2024