

FINISH LEGEND:

DECOR SERIES #700 (ARTISAN DECOR)

SEE THE JSA CONSTRUCTION DRAWINGS AND PROJECT SPECIFICATIONS. SEE PROJECT SPECIFICATIONS SECTION 01 61 27 "DECOR INTERIOR FINISHES AND COLORS - ARTISAN" FOR INFORMATION ON THE FINISHES AND DECOR. COORDINATE EXTENT OF FINISH AND DECOR WORK WITH DECOR DRAWINGS BY OTHERS AND THE KROGER PROJECT MANAGER.

GENERAL NOTES

- A. THIS DRAWING SET IS TO BE VIEWED AS A WHOLE. ALL WORK PERTAINING TO A SPECIFIC TRADE MAY OR MAY NOT BE SHOWN ON SPECIFIC DRAWING OR SPECIFICATION SECTIONS.
- B. THIS PROJECT SHALL CONTAIN A COMPLETE FIRE PROTECTION SPRINKLER SYSTEM. THE EXISTING SYSTEM IN PLACE IS TO BE MODIFIED ACCORDINGLY TO WORK WITH THE NEW CONFIGURATION & LAYOUT. THIS SYSTEM IS TO BE DONE AS A DESIGN BUILD SYSTEM AND HANDLED AS A DEFERRED SUBMITTAL. THE SYSTEM MUST BE DESIGNED BY A LICENSED FIRE SUPPRESSION ENGINEER. SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
- C. SEE KROGER PROJECT MANAGER, SPECIFICATIONS, AND DECOR PLANS FOR DECOR & PAINTING INSTRUCTIONS.
- D. SEE A4.1 FOR TOILET ACCESSORIES & MOUNTING HEIGHTS. ALL ACCESSORIES SHALL BE ICC ANSI A117.1-2009 COMPLIANT.
- E. FIELD VERIFY ALL DIMENSIONS. ALL DIMENSIONS ARE CLEAR UNLESS NOTED OTHERWISE.
- F. ALL DOOR OPENINGS SHALL BE 4" FROM FACE OF ADJACENT PARTITION, UNLESS INDICATED OTHERWISE.
- G. ALL WOOD STUDS, FURRING, BLOCKING, FRAMING AND PLYWOOD SHEATHING SHALL BE FIRE RETARDANT PRESSURE TREATED.
- H. CONSTRUCTION SHALL MEET THE BARRIER FREE REQUIREMENTS STATED IN THE MICHIGAN DEPT. OF LABOR CONSTRUCTION CODE GENERAL RULES, LATEST EDITION.
- I. SEE SHEET A5.2 FOR PARTITION TYPES. MAY DENOTE STUD SIZE, WALL HEIGHT OR SOFFIT HEIGHT.
- J. G.C. TO PROVIDE ALL PLUMBING, MECHANICAL AND ELECTRICAL WORK REQUIRED TO COMPLETE THE PROJECT. SIZE AND LOCATIONS OF PLUMBING, MECHANICAL AND ELECTRICAL FIXTURES AND FITTINGS ARE SHOWN ON THESE DOCUMENTS FOR DESIGN CHARACTERISTICS AND LAYOUT PREFERENCE ONLY.
- K. ALL MATERIAL SHALL BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS. CONTRACTORS TO PROVIDE ALL WARRANTIES AND MATERIALS DURING INSTALLATION.
- L. DIMENSIONS OF ALL COLUMNS ARE BASED ON EXISTING DRAWINGS AND ARE TO BE VERIFIED.
- M. (A) INDICATES TO ALIGN WITH THE ADJACENT, EXISTING WALL.
- N. ALL EXISTING CONTROL JOINTS IN GYPSUM SOFFITS AND WALLS ARE TO BE CONTINUED DOWN INTO NEW INFILL.
- O. PROVIDE ALL NEW CONTROL JOINTS IN GYPSUM SOFFITS, WALLS, AND FURRING AS RECOMMENDED BY THE GYPSUM MANUFACTURER.
- P. UNLESS OTHERWISE NOTED, FOR MASONRY OPENINGS, FURNISH:
- ONE (1) ANGLE 4" X 3 1/2" X 1/4" FOR EACH 4" OF WALL THICKNESS FOR SPANS UP TO 5'-0"
 - ONE (1) ANGLE 5" X 3 1/2" X 5/16" FOR EACH 4" OF WALL THICKNESS FOR SPANS UP TO 7'-0"
- N. CLEAN ALL EXISTING ITEMS MOUNTED TO THE CEILINGS THAT ARE TO REMAIN (IE. HVAC GRILLES & DIFFUSERS, DUCTS, CEILING FANS, EXIT LIGHTS & SIGNS, ETC). REPAIR/REPLACE DAMAGED ITEMS.
- O. CLEAN AND PAINT MISCELLANEOUS WALL ITEMS (IE. CONDUIT, PANELS, & OTHER ITEMS IN OR ON WALLS) TO MATCH ADJACENT WALL FINISH.
- P. REPAIR AND/OR REPLACE ALL SHEATHING, FRAMING AND/OR FINISHES AS REQUIRED DUE TO DEMOLITION WORK. COORDINATE WITH ALL DEMOLITION PLANS (ARCHITECTURAL, MECHANICAL, PLUMBING, & ELECTRICAL).

PARTITION KEY

EXISTING WALL	EXISTING SOFFIT
NEW WALL	NEW SOFFIT

- SEE SHEET A4.1 FOR PLAN NOTES.
- SEE SHEET 11.4 FOR FINISHES DECOR, MILLWORK, & FIXTURE / CASE NOTES.

ALL EXISTING DIMENSIONS ARE BASED OFF OF DRAWINGS AND INFORMATION PROVIDED TO US BY THE KROGER COMPANY. FIELD VERIFY EXISTING CONDITIONS.

ISSUED FOR: BIDS AND PERMITS
DIRECT BUY QUOTE
90% OWNER REVIEW

03/05/2024
02/16/2024
01/25/2024

PROPOSED MINOR INTERIOR REMODEL FOR:



STORE NO. D-711
7084 MILLER ROAD
SWARTZ CREEK, MI 48473

THE KROGER CO. OF MICHIGAN

jeffery a. scott
architects p.c.

32316 grand river ave. suite 200
farmington, michigan 48336-3261
(248) 476-8800 fax (248) 476-8833

FLOOR PLAN


project no.

23086

sheet no.

A1.1

copyright © 2024



TOILET ROOM NOTES:
1. KROGER TO PROFESSIONALLY DEEP CLEAN ALL TOILET ROOMS, INCLUDING THE FLOOR, WALLS AND CEILINGS.

PROVIDE POWER FOR FUTURE PICKUP SIGN (BY OTHERS). COORDINATE LOCATION WITH KROGER P.M. SEE ELECTRICAL.

FLOOR PLAN
SCALE: 3/32" = 1'-0"

G.C. TO PATCH / REPAIR MASONRY WALL WHERE SIGNS HAVE BEEN REMOVED, AS REQUIRED. COORDINATE WITH KROGER P.M. SIGN WORK BY KROGER. (TYP)