

NOTES

1. ALL HVAC SENSORS (I.E. ANALOG TEMPERATURE SENSORS, RELATIVE HUMIDITY SENSORS, CO2 SENSORS) TO BE MOUNTED AT 7'-6" ABOVE FINISHED FLOOR.
2. LIGHTING OVERRIDE SWITCHES TO BE MOUNTED AT 6'-4" ABOVE FINISHED FLOOR.
3. A MODBUS REPEATER IS NEEDED AFTER EVERY 32 CASE CONTROLS IN A ~~FLOOR~~ DOOR ALARM OUTPUTS TO BE WIRED TO THE SPARE DIGITAL INPUT OF CASE CONTROLLER. MULTIPLE EVAPORATORS IN A BOX SHOULD BE DAISY-CHAINED TOGETHER.
4. ISLAND DESIGNATED AS DUAL TEMP WILL HAVE AN OEM INSTALLED TOGGLE SWITCH ON EACH SECTION WIRED TO THE RESPECTIVE CASE CONTROLLER SPARE DIGITAL INPUT.



Issued for:	BIDS AND PERMITS	01/12/2022
	90% OWNER REVIEW	12/14/2022

EM-2B