



VENDOR BID GENERAL NOTES:

- VENDOR SHALL REVIEW COMPRESSOR SELECTIONS STATED ON THE R1.1 REFRIGERATION EQUIPMENT PLAN. ANY DEVIATION FROM THIS AREA MUST BE APPROVED BY THE KROGER CO. VENDOR SHALL PROVIDE LINE SIZES TABLE (WHEN APPLICABLE) (SEE KROGER EQUIPMENT SPECIFICATION).
- ALL REMOTE GLASS DOOR AND MULTI-DOCK MERCHANDISERS TO BE TOP PIPED BY GAS SALES NOTED OTHERWISE.
- ALL FOUR AND FIVE DECK MEDIUM TEMPERATURE CASES TO HAVE MIRROR ENDS UNLESS NOTED OTHERWISE.

VENDOR BID KEYNOTES:

- ① FEATURES SHALL BE ORDERED AND PURCHASED SEPARATELY BY THE KROGER PROJECT MANAGER
- ② CASE END GUARDS SUPPLIED BY MANUFACTURER

INSTALLER GENERAL NOTES:

- LOCATION OF PVC RISERS FOR THE ROUTING OF REFRIGERATION LINES, SHOWN ON PLAN, ALTERNATE ROUTING MAY BE REQUIRED. FIELD CONDITIONS TO BE REVIEWED FOR COMPLEX CASE. CARE SHOULD BE TAKEN IN ROUTING OF LINES TO MINIMIZE INTERFERENCE WITH SHOUT OFFENSIVE. REFRIGERATION LINES SHALL BE NOTED AS HIGH AS PRACTICAL.
- EXISTING REFRIGERATION PIPING TO BE REAPPLIED WHERE PRACTICAL. ITS THE INSTALLER'S RESPONSIBILITY TO REPLACE EXISTING PIPING AND INSULATION AS REQUIRED TO CONFORM TO THE REFRIGERATION CONDENSING EQUIPMENT MANUFACTURER'S RECOMMENDATIONS FOR THE REFRIGERATION LOAD SERVED.

INSTALLER KEYNOTES:

- ③ LOCATION OF REFRIGERATION PIPING RISER, REFERENCE RISD-36 & RISD-36A
- ④ INSTALL SELF-CONTAINED EQUIPMENT

CONTROL NOTE:

- ANY NEW CIRCUIT CONTROLS REQUIRED TO ACCOMPLISH REMODEL TO BE SIZED AND PROVIDED BY REFRIGERATION INSTALLER. SUITABILITY OF RE-ARMED EXISTING CONTROLS FOR MODIFIED SYSTEMS TO BE DETERMINED BY REFRIGERATION INSTALLER. VERIFY VOLTAGE, FREQUENCY AND OPERATION WHEN NEW LOADS DIFFER FROM EXISTING. CONTROLS TO BE INSTALLED IN ACCESSIBLE LOCATIONS PROTECTED FROM DAMAGE.

SHEET INDEX:

- R1.1 (THIS SHEET) REFRIGERATION EQUIPMENT PLAN
- R1.2 REFRIGERATION STANDARD DETAILS
- R1.3 REFRIGERATION EQUIPMENT SCHEDULE

LEGEND:

- ⑤ TEMPERATURE SENSOR
- ⑥ DEFROST TERMINATION THERMOSTAT

COLOR KEY

- EXISTING FIXTURES
- RELOCATED FIXTURES
- NEW FIXTURES
- R&S FIXTURES

CURRENT PLAN DATE: 8/10/2023	
ORIGINAL PLAN DATE: 8/10/2023	
DRAWN: B. AUGUSTUS	CHECKED: M. GIGLIO
REVISIONS:	
STANDARD PLOTTED SCALE: 1/16"=1'-0"	
BUILDING STATS:	
TOTAL SHELVING:	2,682 LF
SALES AREA:	42,708 SF
BASE STORE:	55,705 SF
MEZZANINE:	3,014 SF
GROSS BUILDING 58,718 SF	
REFRIGERATION EQUIPMENT LAYOUT	
STEEL PACKAGE ID: Not Applicable	
N-856	
R1.1	
CAD FILE: 20-NR56_R1.1-REFRIGERATION	

General Notes

1. REFER TO ASD-159 FOR REFRIGERATION FIT REQUIREMENTS.
2. REFRIGERATION CONTRACTOR TO INSTALL KICKPLATE, BUMPERS AND TAG MOLDING ON REFRIGERATED CASES.

#	Date	Change Description

KROGER N856
FOSTORIA
126 WEST HIGH STREET
FOSTORIA, OHIO 44830

for
THE KROGER COMPANY

Moody Nolan

300 Service Street
Suite 300
Columbus, Ohio 43215

Phone: (614) 461-4664
Fax: (614) 280-8861
www.moodynolan.com

Dwg. Coord.: JWB Tech. Coord.: Proj #: 23016.09

**REFRIGERATION
EQUIPMENT LAYOUT**

BID/PERMIT

R1.1

2/2/24