


OWNERSHIP OF INSTRUMENTS OF SERVICE
All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by the Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright therein.

© 2010 Moody Nolan, Inc.



1 ELECTRICAL POWER DIMENSION PLAN
3/32" = 1'-0"

GENERAL DIMENSION NOTES

- REFER TO EQUIPMENT SCHEDULES ON SHEET E6.2 FOR MOUNTING HEIGHTS AND ADDITIONAL INFORMATION. ALSO SEE DETAILS ON SHEET E5-SERIES DRAWINGS WHERE APPLICABLE.
- ALL DIMENSIONS INDICATED ON PLANS THAT ARE FROM INTERIOR PARTITIONS WHERE THE RETURN AIR SHAFT IS INDICATED ARE TAKEN FROM THE SALES AREA SIDE OF THE ROOF DECK HIGH PARTITION, NOT THE RETURN AIR SHAFT PARTITION.
- FIELD COORDINATE UNDERSLAB CONDUIT AND RACEWAY LAYOUTS WITH ALL AFFECTED PARTIES PRIOR TO SLAB PLACEMENT.
- FLUSH MOUNT ALL WALL OUTLETS IN FOOD PREP AREAS. OUTLETS LOCATED ABOVE STAINLESS STEEL TABLES SHALL BE A MINIMUM OF 46" AFF. MOUNT ALL WALL OUTLETS IN ALL PREP AREAS HORIZONTALLY.
- PROVIDE 10 FEET OF SEAL-TIGHT FLEXIBLE CONDUIT FOR REFRIGERATED CASES SERVED FROM WALL JUNCTION BOXES FOR ISLAND REFRIGERATED CASES FOR CONNECTION TO CASES BY THE PHASE II EQUIPMENT CONTRACTOR.
- DIMENSIONAL WORK INDICATED SHALL BE SCHEMATICALLY TYPICAL FOR ALL RELATED WORK INCLUDING CORRESPONDING WORK SHOWN ON EHS PLANS.
- ALL ELECTRICAL AND COMMUNICATION JUNCTION/OUTLET BOXES SHOWN AGAINST THE WALL SHALL BE MOUNTED IN THE WALL. REFER TO THE ELECTRICAL EQUIPMENT SCHEDULE FOR MOUNTING INFORMATION.
- IN GENERAL, RECEPTACLES SHOWN WITHOUT EQUIPMENT MARKINGS OR OTHER CALLOUT ARE CONVENIENCE OUTLETS THAT SHALL BE MOUNTED AT 18" AFF.
- ALL DIMENSIONS SHOWN ON DIMENSION DRAWINGS ARE SHOWN AS A CONVENIENCE REFERENCE FOR THE ELECTRICAL CONTRACTOR. THE ELECTRICAL CONTRACTOR SHALL COORDINATE AND FIELD VERIFY ALL DIMENSIONAL WORK WITH RESPECTIVE EQUIPMENT AND WITH ALL AFFECTED PARTIES PRIOR TO ROUGH-IN.
- SEE DETAIL "F" ON E5-SERIES DRAWINGS FOR SPECIAL CIRCUITING AND DIMENSIONING REQUIREMENTS THAT APPLY TO REFRIGERATED CASE EQUIPMENT.



KOHRIS LONNEMANN HEIL ENGINEERS, INC.
MECHANICAL/ELECTRICAL ENGINEERS

WWW.KLHENGERS.COM

1538 ALEXANDRIA PIKE, SUITE 111
FT. THOMAS, KENTUCKY 41075

603-254-9783

859-442-8590

859-442-8558 FAX

LEXINGTON, KENTUCKY
LOUISVILLE, KENTUCKY
COLUMBUS, OHIO

OWNERSHIP OF INSTRUMENTS OF SERVICE

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by the Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright therein.

| # | Date | Change Description |
|---|------|--------------------|
| | | |
| | | |
| | | |
| | | |

KROGER N856
 126 W HIGH ST
FOSTORIA, OH 44830
for
THE KROGER COMPANY



300 Spruce Street
Suite 300
Columbus, Ohio 43215

Phone: (614) 461-4664
Fax: (614) 293-8881
www.moodynolan.com

| | | |
|------------------|-------------------|------------------|
| Dwg. Coord.: CJC | Tech. Coord.: LGF | Proj #: 25778.00 |
|------------------|-------------------|------------------|

| | |
|--|---------------|
| ELECTRICAL POWER DIMENSION PLAN | E1.5.2 |
|--|---------------|

| | |
|------------------|------------|
| 95% OWNER REVIEW | 10/27/2023 |
|------------------|------------|