

OWNERSHIP OF INSTRUMENTS OF SERVICE
All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by the Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright therein.

© 2010 Moody Nolan, Inc.

KEYED NOTES

TV MONITOR OUTLETS

IN ADDITION TO ALL OTHER ELECTRICAL WORK SHOWN ON DRAWINGS, PROVIDE ONE (1) OUTLET BOX AND ONE (1) 1" EMPTY CONDUIT EACH, FOR UP TO EIGHT (8) TELEVISION MONITORS THAT WILL BE INSTALLED AT VARIOUS LOCATIONS THROUGHOUT THE FACILITY. DETERMINE EXACT LOCATIONS IN FIELD.


VOICE/DATA OUTLET SCHEDULE

PROVIDE EMPTY CONCEALED GALVANIZED STEEL EMT CONDUIT DROP(S) FROM OVERHEAD JOIST SPACE TO VOICE/DATA OUTLET BOXES AS DEFINED IN THIS SCHEDULE. PROVIDE INSULATED THROAT FITTINGS (OR BUSHINGS), SWEEP BENDS AND 200W DRAG LINES. PROVIDE 4" SQUARE X 2-1/8" DEEP OUTLET BOX FOR ALL APPLICATIONS. INSTALL FLUSH MOUNTED WHEREVER POSSIBLE. INSTALL AT 1' ABOVE FINISHED FLOOR UNLESS INDICATED OTHERWISE. PROVIDE SINGLE-GANG RING FOR UP TO FOUR (4) TOTAL JACKS AND TWO-GANG RING FOR UP TO EIGHT (8) JACKS. PROVIDE QUANTITIES OF CONDUIT DROPS AS REQUIRED.

| QUANTITY OF VOICE/DATA JACKS SERVED | MINIMUM CONDUIT SIZE REQUIRED |
|-------------------------------------|-------------------------------|
| 2 | 3/4" |
| 4 | 1" |
| 8 | 1-1/4" |
| 12 | 1-1/2" |

GENERAL MISCELLANEOUS SYSTEMS NOTES

- ALL RACEWAYS AND BOXES FOR CT DEVICES SHALL BE PROVIDED BY BEC. DEVICES TO BE PROVIDED BY OTHERS. PROVIDE PULL STRINGS & END BUSHINGS IN ALL RACEWAYS. ALL CONDUIT FOR DATA DROPS STUBS UP ABOVE ACCESSIBLE CEILING.
- REFER TO EQUIPMENT SCHEDULE ON SHEET E6.2 FOR MOUNTING HEIGHTS AND ADDITIONAL INFORMATION. ALSO SEE DETAILS ON SHEET E5-SERIES DRAWINGS WHERE APPLICABLE.
- COORDINATE THE UNDERSLAB CONDUIT/RACEWAY LAYOUT WITH ALL AFFECTED PARTIES PRIOR TO SLAB PLACEMENT.
- THE FOLLOWING APPLIES FOR ALL KITCHEN AND FOOD PREP TYPE AREAS. INSTALL ALL WALL OUTLETS RECESSED. FLUSH MOUNTED. INSTALL ALL OUTLETS LOCATED ABOVE STAINLESS STEEL TABLES AT 48" AFF. MOUNT ALL WALL OUTLETS IN ALL PREP AREAS HORIZONTALLY. DO NOT INSTALL OUTLETS WHERE GYPSUM BOARD MEETS WALL TILE. EITHER INSTALL FULLY IN GYPSUM BOARD OR IN WALL TILE.
- IN ADDITION TO REQUIREMENTS SET FORTH UNDER NOTE E ABOVE, PROVIDE WEATHERPROOF (NEMA 3R WHILE IN USE) OUTLETS IN PRODUCE PREP AND MEAT PREP.
- REFER TO ELECTRICAL DIMENSION PLANS FOR GENERAL DIMENSIONAL INFORMATION THAT SHALL SCHEMATICALLY APPLY FOR CORRESPONDING SYSTEMS WORK.



PHONE DATA SPECIALTY
3/32" = 1'-0"



KOHRIS LONNEMANN HEIL ENGINEERS, INC.
MECHANICAL/ELECTRICAL ENGINEERS

WWW.KLHENGRS.COM

1538 ALEXANDRIA PIKE, SUITE 111
FT. THOMAS, KENTUCKY 41075
859-442-8590
859-442-8595 FAX

LEXINGTON, KENTUCKY
LOUISVILLE, KENTUCKY
COLUMBUS, OHIO

OWNERSHIP OF INSTRUMENTS OF SERVICE

All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by the Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright therein.

| # | Date | Change Description |
|---|------|--------------------|
| | | |
| | | |
| | | |
| | | |

KROGER N856



126 W HIGH ST
FOSTORIA, OH 44830

for THE KROGER COMPANY



300 Spruce Street
Suite 300
Columbus, Ohio 43215

Phone: (614) 461-4684
Fax: (614) 290-8881
www.moodynolan.com

Dwg. Coord.: CJC Tech. Coord.: LGF Proj. #: 25778.00

PHONE DATA SPECIALTY

ET1.1

95% OWNER REVIEW

10/27/2023